



## SHRI SAIBABA SANSTHAN TRUST, SHIRDI

Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India) Telephone: +91-2423-258 500, Fax: +91-2423-258 770, Telegram: Sainath, Shirdi.

NO.SSST/CONST/ Date: 1879

To,

3 1 AUG 2021

...2/-.

Sub: Notice Inviting Quotation for Internal Painting & Aluminium Door Work for Shri Sainath Blood Bank at Shri Saibaba Hospital, Shirdi.

Dear Sir.

Sealed item rate quotations are invited for the following work at Shirdi, subject to the terms and conditions mentioned below,

A) Bill of Quantities:

Sr.No.	Description	Qty.	Unit
1	Scraping out white wash or colour wash or distemper by steel wire brushing and/ or scrapping by paper and preparing the wall surface smooth including necessary repairs to scratches, applying putty etc. competed. Additional Item Spec. No. As directed by Engineer in charge. B) Scrapping out old colour by steel wire brushing with applying wall putty.	915.90	Sqm
2	Providing and applying priming coat on concrete/ masonry / Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	915.90	Sqm
3	Providing and applying plastic emulsion paint of approved quality, colour and shade to old and new surfaces in two coats including scaffolding, preparing the surface. (excluding the primer coat) etc. complete.	915.90	Sqm
4	Providing and applying two coats of synthetic enamel paint of approved colour to new / old structural steel work and wood work in buildings including if necessary. Cleaning and preparing the surface (excluding primer coat) complete. (Sample and brand is to be approved from Executive Engineer before use).	100.00	Sqm
5	Providing and fixing in position, Single shuttered aluminium extruded powder coated openable door of overall size 0.90 m x 2.40m with aluminium door frame of powder coated section 101.60 x 44.75mm, 3.18mm thick and shutter comprising of powder coated section having bottom and lock rail of size 150mm x 44.5mm x 3.00mm thick top rails 47.62 x 44.45mm x 3.00mm thick, vertical style 47.62 x 44.45mm, 3.00mm thick and for shutter plain glass panes 5mm thick for top panels and 12mm thick both side laminated phenol bonded particle board panels for bottom panels etc., I.S.I. mark, with bijagiri having heavy duty concealed lock, necessary beading, glazing clips, PVC gaskets, 250mm length tower bolts, 150mm dia. pad handle, heavy duty door closer of approved brand etc. as per detailed design and drawing or as directed by engineer in charge including all materials, labours and equipment etc. complete. SSR Item No.39.65.	8.31	Sqm



Sainiketan, 804, - B, Dr. Ambedkar Marg, Dadar, Mumbai - 400 014

Telephone: + 91-22-24166556, Fax: + 91-22-24150798, Telegram: Sainiketan, Mumbai.

http://www.shrisaibabasansthan.org / www.sai.org.in • E\_mail : saibaba@sai.org.in

## B) Terms and Conditions:

- The rates for above work shall be inclusive of GST, material, labour, transport etc. complete.
- 2. The bidder shall furnish the copy of GST Registration.
- The rates quoted shall be firm & no escalation of rates will be entertained till completion of work after issue of work order.
- 4. Defects Liability period will be for 12 months for above mentioned work.
- 5. Quantities in BOQ are approximate and may vary according to the requirement. Bill will be paid as per the measurement of actual work executed on site.
- 6. No advance payment will be given against the work order. Bill will be paid after submission of R. A. bill / Final Bill and as per the actual quantity executed on site.
- 7. 75% Advance will be payable on submission of R. A. Bill.
- 8. Value of Interim Bill Certificate is Rs.1,00,000/-.
- 9. The date of commencement shall be 07 days from date of issue of work order.
- 10. The time for completion shall be 30 days from the date of commencement after issue of work order.
- 11. Material shall be strictly used as per the specifications and makes with prior approval of Sansthan.
- 12. Electricity required for the work shall be made available at one point by Sansthan.
- 13. 5% Total Security Deposit will be recovered from the bills. Which will be returned after 12 months of DLP.
- 14. Validity of quotation 90 days from last date for submission of sealed quotation and to be extended if required.
- 15. Liquidated Damages The liquidated damages to be recovered will be Rs.500/- per delayed day. The total amount of Liquidated damages / Penalty to be paid under the provisions of this clause shall not exceed five percent (5%) of the total Contract amount.
- 16. The bidders are requested to submit their Bank details (RTGS) along with the quotation document.
- 17. Bidders are requested to submit the final lowest rates for this work.
- 18. The quotation shall be written on a letterhead of your firm and shall be submitted in a sealed cover superscribing as "Quotation for Internal Painting & Aluminium Door Work for Shri Sainath Blood Bank at Shri Saibaba Hospital, Shirdi". The reference no. & date of this NIQ shall be mentioned on the envelope. It shall be addressed to Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi, Tal.- Rahata, Dist.-Ahmednagar.
- 19. Your quotation should reach at our Shirdi Office immediately after receipt of this NIQ.

## C) Makes:

- 1) Cement Ultra Tech, Ambuja, Birla Gold, ACC (If required).
- 2) Luster Paint Asian, Berger, Dulux, Nerolac.
- 3) Plastic Emulsion Paint Asian, Nerolac, Dulux, Berger.
- 4) Primer Asian, Berger, Dulux, Nerolac.
- 5) Synthetic Enamel Paint Asain Apcolite, Nerolac Highgloss, Berger, Dulux Highgloss.
- 6) Aluminium Door Section Jindal, Hindalco.
- 7) Door Closer & Accessories Godrej, Hettich, Dorma, Haffle.

Shri Saibaba Sansthan Trust, Shirdi reserves the right to reject any or all quotations without assigning any reasons therefor.

Thanking you.

S. M. Jori)

I/c Executive Engineer, Shri Saibaba Sansthan Trust, Shirdi.