

**SHRI SAIBABA SANSTHAN TRUST, SHIRDI**

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)
Telephone : +91-2423-258 500, Fax : +91-2423-258 770, Telegram : Sainath, Shirdi.

NO.SSST/CONST/
Date: 17/9/2021.

26 AUG 2021

To,

Sub: Notice Inviting Quotation for Providing & Laying Granite Flooring and Other Miscellaneous Civil works in General OT – 01 & 02 of Shri Saibaba Hospital, Shirdi.

Dear Sir,

Sealed item rate quotations are invited for the following work at Shirdi, subject to the terms and conditions mentioned below,

A) Bill of Quantities:

Sr. No.	Description	Quantity	Unit
1	Removing cement tiles or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete. SSR I.No.46.19. P.No.284.	75.00	Sqm
2	Carting away unwanted dismantle material from the site upto 2 kms.	8.00	Cum
3	Providing and laying in position flooring of Imperial White / Kashmir White/ Moon White/ Amba White granite stone of approved shade and size 18 mm to 20 mm thick on bed 1:6 cement mortar including cement floats striking joints, pointing in CM 1:3 curing and cleaning etc. complete. SSR I.No.33.34, P.No.208.	75.00	Sqm
4	Providing and laying in position flooring of Imperial White / Kashmir White/ Moon White/ Amba White granite stone of approved shade and size 18 mm to 20 mm thick on bed 1:6 cement mortar including cement floats striking joints, pointing in CM 1:3 curing and cleaning etc. complete. (Skirting). SSR I.No.33.34, P.No.208.	5.20	Sqm
5	Providing and fixing in position, Single shuttered aluminium extruded powder coated openable door of overall size 0.90 m x 2.40 m with aluminium door frame of powder coated section 101.60 x 44.75mm, 3.18 mm thick and shutter comprising of powder coated section having bottom and lock rail of size 150 mm x 44.5 mm x 3.00 mm thick top rails 47.62 x 44.45 mm x 3.00 mm thick, vertical style 47.62 x 44.45 mm, 3.00 mm thick and for shutter plain glass panes 5 mm thick for top panels and 12mm thick both side laminated phenol bonded particle board panels for bottom panels etc., I.S.I. mark, heavy duty, Hydraulic floorspring of 150 Kilogram capacity, having heavy duty concealed lock, necessary beading, glazing clips, PVC gaskets, 250mm length tower bolts, 150mm diam. pad handle, etc. as per detailed design and drawing or as directed by engineer in charge including all materials, labours and equipment etc. Complete.	6.300	Sqm
6	Providing and applying priming coat over new/old steel and other metal surfaces including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and scoured with wire brushes, fine steel wool, scrappers and sand paper, scaffolding etc. complete. SSR I.No.35.20, P.No.216. (For Walls Upto 1.0 Mtr. Ht.).	45.00	Sqm
7	Providing and applying pearl / luster finish paint of approved colour and shade to the existing plaster surface including scaffolding, preparing the surface, applying the acrylic wall putti etc. complete. SSR I.No.35.23, P.No.217. (For Walls Upto 1.0 Mtr. Ht.).	45.00	Sqm

..2/-.



...2...

B) Terms and Conditions:


1. The rates for above work shall be inclusive of GST, material, labour, transport etc. complete.
2. The bidder shall furnish the copy of GST Registration.
3. The rates quoted shall be firm & no escalation of rates will be entertained till completion of work after issue of work order.
4. Defects Liability period will be for 12 months for above mentioned work.
5. Quantities in BOQ are approximate and may vary according to the requirement. Bill will be paid as per the measurement of actual work executed on site.
6. No advance payment will be given against the work order. Bill will be paid after submission of R. A. bill / Final Bill and as per the actual quantity executed on site.
7. 75% Advance will be payable on submission of R. A. Bill.
8. Value of Interim Bill Certificate is Rs.2,00,000/-.
9. The date of commencement shall be 07 days from date of issue of work order.
10. The time for completion shall be 30 days from the date of commencement after issue of work order.
11. Material shall be strictly used as per the specifications and makes with prior approval of Sansthan.
12. Electricity required for the work shall be made available at one point by Sansthan.
13. 5% Total Security Deposit will be recovered from the bills. Which will be returned after 12 months of DLP.
14. Validity of quotation - 90 days from last date for submission of sealed quotation and to be extended if required.
15. Liquidated Damages - The liquidated damages to be recovered will be Rs.500/- per delayed day. The total amount of Liquidated damages / Penalty to be paid under the provisions of this clause shall not exceed five percent (5%) of the total Contract amount.
16. The bidders are requested to submit their Bank details (RTGS) along with the quotation document.
17. Bidders are requested to submit the final lowest rates for this work.
18. The quotation shall be written on a letterhead of your firm and shall be submitted in a sealed cover superscribing as "**Quotation for Providing & Laying Granite Flooring and other Miscellaneous Civil works in General OT - 01 & 02 of Shri Saibaba Hospital, Shirdi**". The reference no. & date of this NIQ shall be mentioned on the envelope. It shall be addressed to Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi, Tal.- Rahata, Dist.- Ahmednagar.
19. Your quotation should reach at our Shirdi Office immediately after receipt of this NIQ.

C) Makes:

- 1) Cement – Ultra Tech, Ambuja, Birla Gold, ACC.
- 2) Tile Adhesive – Sika, Ultra Tech, ACC, Perma, Asian Paints, Dr. Fixit, Ascolite or Equivalent.
- 3) Vitrified / Ceramic Tiles – If required will be supplied by Sansthan.
- 4) Luster Paint – Asian, Berger, Dulux, Nerolac.
- 5) Primer - Asian, Berger, Dulux, Nerolac.
- 6) Door Accessories – Godrej, Hettich, Dorset or Equivalent.
- 7) Door Closer – Godrej, Hettich, Dorset or Equivalent.

Shri Saibaba Sansthan Trust, Shirdi reserves the right to reject any or all quotations without assigning any reasons therefor.

Thanking you.


(S. M. Jori)

**I/c Executive Engineer,
Shri Saibaba Sansthan Trust, Shirdi.**